



CALAMBA WATER DISTRICT

Lakeview Subdivision, Halang, Calamba City, Laguna
Tel. Nos. 545-1614; 545-2863; 545-2728; 545-7895; Fax No. 545-9752
www.cwd.com.ph



PHIP QMS 21 53 0047

PROJECT: Supply of Labor and Materials for the installation of Awning Canopy
Roof
SUBJECT: Scope of Works and Specification
LOCATION: CWD Extension Office, Brgy. Canlubang, Calamba City
DATE: October 9, 2025

Scope of Works

1. Construct new canopy as per plan
2. Apply metal primer paint for all metal installed
3. Tie rod assemblies include clevises, turnbuckles, nuts, washers, and anchor plates

Specifications

A. Miscellaneous includes

- | | |
|--------------------------------|-----------------------|
| 1. Electric Hand Drill | 6. Level Hose |
| 2. Aviation Metal Snip Scissor | 7. Meter tape |
| 3. Manual Riveter | 8. Cutting Disk |
| 4. Plier | 9. Metal Primer Paint |
| 5. Hammer | |

B. Tubular bar

- | | | |
|-----------|---|-------------------|
| Depth | : | 4 feet |
| Breadth | : | 2 feet |
| Thickness | : | 2.0mm |
| Length | : | 6 meters |
| Material | : | Steel (ASTM A500) |
| Shape | : | Rectangular |


C. Tie rod assemblies

- | | | |
|----------|---|----------------------------|
| Diameter | : | 16mm |
| Material | : | Steel (ASTM A325) |
| Length | : | Customized (as per actual) |

D. Fiber Glass Roofing

- | | | |
|---------------|---|---------------------|
| Nominal Width | : | 4 feet |
| Length | : | 8 feet |
| Thickness | : | 6 mm |
| Materials | : | Polyester resin |
| Color | : | Clear / Transparent |


Prepared by:


ENGR. MA ANGELICA C. AVILLANOSA
Principal Engineer C

Checked by:


ENGR. ROLANDO V. BARO
OIC - DM - TSD - PMD

Recommending for Approval by:


ENGR. RANELY S. CARTAGO
TSD - Department Manager

Approved by:


MR. EXEQUIEL A. AGUILAR JR.
General Manager